

STRATHAM

STEARNS (54)

CA 2005070310

7

App

Cherry
Tham

1345

5/23/08

P.V.

APPROVAL FOR CONSTRUCTION

CA2005070310

N.H. DEPARTMENT OF ENVIRONMENTAL SERVICES
SUBSURFACE SYSTEMS BUREAU
P.O. BOX 95, 29 HAZEN DRIVE, CONCORD, NH 03302-0095

APPROVAL NO.

CA2005070310

THE PLANS AND SPECIFICATIONS FOR SEWAGE OR WASTE DISPOSAL SYSTEM SUBMITTED FOR:

OWNER:

RICHARD STEARNS
PO BOX 14
WARNER NH 03278-

Map No./Lot No.:

18 / 54

Subd. Appvl. No.:

2004005549

Subd. Name:

BATCHELDER TRUST

County:

ROCKINGHAM

Registry Book No.:

4353

Registry Page No.:

443

Probate Docket No.:
(If Applicable)

0

COPY SENT TO:

TOWN OF STRATHAM
10 BUNKER HILL AVE
STRATHAM NH 03885

Type of System:

3 BR
450 GPD

Town/City Location:

STRATHAM

BY APPLICANT: PERMIT NO.

00064

Street Location:

54 UNION ROAD

JEFFREY A EVANS
PO BOX 522
SOUTH SUTTON NH 03273

Subsurface waste disposal systems must be operated and maintained in a manner so as to prevent nuisance or health hazard due to system failure.
(RSA 485-A:37)

It is unlawful to discharge any hazardous chemicals or substances into subsurface waste disposal systems. Included are paints, thinners, gasoline and chlorinated hydrocarbon solvents such as TCE, sometimes used to clean failed septic systems and auto parts. (Env-Ws 1503.04)

ADVISE YOUR CONTRACTOR OF REQUIRED CHANGES
IN PLANS AS INDICATED BELOW CONDITIONS

03/10/2005

Approved this date: _____

Date amended: _____

By: _____

N.H. Department of Environmental Services Staff

Amended by: _____ (OVER)

REVISED 8/01

200501485

NHDES, SSB FILE

N.H. DEPARTMENT OF ENVIRONMENTAL SERVICES
SUBSURFACE SYSTEMS BUREAU
P.O. BOX 95, 6 HAZEN DRIVE, CONCORD, NH 03302-0095

THIS APPROVAL DOES NOT SUPERSEDE ANY EQUIVALENT OR MORE
STRINGENT LOCAL ORDINANCES OR REGULATIONS, STATE
STANDARDS ARE MINIMAL AND MUST BE MET STATEWIDE.

**IN THE EVENT OF SYSTEM FAILURE, IT SHALL BE THE
RESPONSIBILITY OF THE OWNER TO CORRECT
ANY SUCH FAILURE.**

NO LIABILITY IS INCURRED BY THE STATE by reason of any approval of subdivision plans or any approval to construct or use a sewage or waste disposal system. Approval by the Department of Environmental Services of sewage and waste disposal systems and subdivisions is based on plans and specifications supplied by the applicant.

NO GUARANTEE IS INTENDED OR IMPLIED BY REASON OF
ANY ADVICE GIVEN BY THE DEPARTMENT OR ITS STAFF.

PLEASE POST IN A CONSPICUOUS PLACE DURING CONSTRUCTION

The system must be constructed in strict accordance
with the approved plans and specifications

The installed system must be left uncovered and cannot be used
after construction until it is inspected and
finally approved by an authorized agent
of the Department. This is to make
certain the system is built
according to the approved
plans and specifications.

CONTACT THIS OFFICE: 271-3501, REGIONAL OFFICE, OR OUR
AUTHORIZED LOCAL AGENT, WHEN READY FOR INSPECTION.

This system must be installed by an installer holding a valid permit, except an owner may install the system
for his/her primary domicile.

Env-Ws 1004.09 EXCEPT AS PROVIDED IN Env-Ws 1003.19, ALL CONSTRUCTION APPROVALS ISSUED
BY THE DEPARTMENT SHALL EXPIRE 4 YEARS FROM THE DATE OF ISSUE, UNLESS AN OPERATIONAL
APPROVAL HAS BEEN GRANTED OR IS IMMINENT FOR SUBJECT CONSTRUCTION.

Env-Ws 1003.19 Replacement of Failed Systems. All applications submitted for the purpose of correcting a failed system
shall be accompanied by a written statement from the Town Health Officer confirming that the existing system is in fact
in failure. Construction approvals granted for replacement of a failed system shall be valid for a period of 90 days. Failure
to complete construction within the 90 day approval period shall result in the invalidation of the approval.

APPROVAL FOR OPERATION

CA2005070310

N.H. DEPARTMENT OF ENVIRONMENTAL SERVICES
SUBSURFACE SYSTEMS BUREAU
P.O. BOX 95, 29 HAZEN DRIVE, CONCORD, NH 03302-0095

APPROVAL NO. CA2005070310

AMENDED DUE TO:

OWNER:

RICHARD STEARNS
PO BOX 14
WARNER NH 03278-

Map No./Lot No.: 18 / 54
Subd. Appvl. No.: 2004005549
Subd. Name: BATCHELDER TRUST
County: ROCKINGHAM
Registry Book No.: 4353
Registry Page No.: 443
Probate Docket No.:
(If Applicable)

COPY SENT TO:

TOWN OF STRATHAM
10 BUNKER HILL AVE
STRATHAM NH 03885

Type of System: 0
3 BR
450 GPD
Town/City Location: STRATHAM

Street Location: 54 UNION ROAD

Installer

Chappy Thunro

Permit No.

1345

☐ Owner Installed For His/Her Domicile

Was Inspected On (Date)

5/23/05

Before Covering And Is Hereby Approved For Use.

Date Approved:

5/23/05

By:

Authorized Agent, Of N.H. Department of
Environmental Services

(OVER)

Subsurface waste disposal systems must be operated and maintained in a manner so as to prevent nuisance or health hazard due to system failure.
(RSA 485-A:37)

It is unlawful to discharge any hazardous chemicals or substances into subsurface waste disposal systems. Included are paints, thinners, gasoline and chlorinated hydrocarbon solvents such as TCE, sometimes used to clean failed septic systems and auto parts. (Env-Ws 1503.04)

REVISED 8/01

200501485

NHDES SSB FILE

GOLD = Owner's

YELLOW = Town's

BLUE = NHDES, SSB file

N.H. DEPARTMENT OF ENVIRONMENTAL SERVICES
SUBSURFACE SYSTEMS BUREAU
P.O. BOX 95, 6 HAZEN DRIVE, CONCORD, NH 03302-0095

THIS APPROVAL DOES NOT SUPERSEDE ANY EQUIVALENT OR MORE
STRINGENT LOCAL ORDINANCES OR REGULATIONS, STATE
STANDARDS ARE MINIMAL AND MUST BE MET STATEWIDE.

IN THE EVENT OF SYSTEM FAILURE, IT SHALL BE THE
RESPONSIBILITY OF THE OWNER TO CORRECT
ANY SUCH FAILURE.

NO LIABILITY IS INCURRED BY THE STATE by reason of any approval of subdivision plans or any approval to construct or use a sewage or waste disposal system. Approval by the Department of Environmental Services of sewage and waste disposal systems and subdivisions is based on plans and specifications supplied by the applicant.

NO GUARANTEE IS INTENDED OR IMPLIED BY REASON OF
ANY ADVICE GIVEN BY THE DEPARTMENT OR ITS STAFF.

**NHDES****State of New Hampshire
DEPARTMENT OF ENVIRONMENTAL SERVICES**

Subsurface Systems Bureau

Hazen Drive, P.O. Box 95, Concord, NH 03302-0095

603-271-3501 FAX 603-271-6683

TDD Access: Relay NH 1-800-735-2964

APPLICATION FOR INDIVIDUAL SEWAGE DISPOSAL SYSTEM APPROVAL

FOR OFFICE USE ONLY

Fee Paid 150 Date Received 3/09/05
Check No. 472

FEE \$150.00

Failed System/Replacement _____ Expedite _____
Waiver Request _____ Holding Tank _____

PLEASE PRINT OR WRITE LEGIBLY, COMPLETE ENTIRE FORM

1. System Location:CITY/TOWN: **STRATHAM** CITY/TOWN APPROVAL OBTAINED: Yes MC IF YES/DATE 7 Mar 05STREET/LOCATION **54 UNION ROAD** LOT NO: **54** TAX MAP NO. **18**SUBDIVISION NAME: **BATCHELDER TRUST** REGISTRY BOOK NO: **4353** PAGE NO: **443**STATE APPROVAL NO. **SA2004005549** COUNTY: **ROCKINGHAM** PROBATE NO. _____ (If Applicable)2. Water Supply:MUNICIPAL WATER SUPPLY ☐ COMMUNITY ☐ WELL ON LOT ☐ OTHER ☒3. Lot OWNER'S Name: **RICHARD STEARNS** STREET: **P.O. BOX 14**CITY/TOWN: **WARNER** STATE: **NH** ZIP: **03278** TEL. NO: **456-3315**4. APPLICANT'S Name: **JEFFREY A. EVANS** STREET: **P.O. BOX 522**CITY/TOWN: **SOUTH SUTTON** STATE: **NH** ZIP: **03273** TEL. NO: **927-4696**Designer's Name: **JEFFREY A. EVANS** Permit No. **64** P.E.: _____
(P.E. required if more than 2,500 GPD)5. Amended Plan _____ Revised Plan _____ Previous Construction Approval No. **CA200406776**

THE STATEMENT BELOW MUST BE SIGNED AND DATED BY THE APPLICANT AND OWNER[S]

Owner(s):

THE UNDERSIGNED CERTIFY THAT THEY ARE THE PRESENT OWNERS OF THE PROPERTY BEING APPLIED FOR AND THAT THEY HAVE SEEN THE PLANS AND THEY ARE IN ACCORDANCE WITH THEIR NEEDS AND DESIRES. THE UNDERSIGNED FULLY UNDERSTANDS THAT SHOULD THIS PLAN BE APPROVED, NO WAIVERS TO THE CONSTRUCTION APPROVAL WILL BE ALLOWED. ANY CHANGES WILL REQUIRE A NEW SUBMISSION (WITH FEE), REVIEW AND APPROVAL.

Date: 2-28-05 Signed: [Signature] 2-28-05
Owner(s)

Applicant:

To the best of my knowledge, the data and information which I have submitted to obtain approval for construction from the New Hampshire Department of Environmental Services is true and correct. I understand that an approval based upon incorrect data may be subject to revocation. I also understand that NO CONSTRUCTION OF ANY STRUCTURE SERVICED BY THE PROPOSED SYSTEM, NOR THE SYSTEM ITSELF, MAY COMMENCE WITHOUT PRIOR WRITTEN DEPARTMENT APPROVAL. I HAVE COMPLIED WITH ALL LOCAL REGULATIONS OR ORDINANCES RELATIVE TO CONSTRUCTION OF SEWAGE DISPOSAL SYSTEMS AND HAVE OBTAINED ALL OTHER APPROVALS THAT MAY BE REQUIRED FOR OTHER WORK RELATED TO CONSTRUCTION OF THE SEWAGE DISPOSAL SYSTEM. The applicant herewith certifies, where applicable, that the approved off-site, municipal or community, water supply is available at the lot line.

Date: 2-28-05 Signed: [Signature] cd
Applicant Permit No.**Shoreland Protection Certification**Introduction

The New Hampshire Shoreland Protection Act (RSA 483-B) requires that applicants for environmental permits which involve work in the protected shoreland "demonstrate to the satisfaction of the department (of environmental services) that the proposal meets or exceeds the development standards of this chapter." The certification contained herein is an acceptable vehicle for such a demonstration.

The protected shoreland is defined to be all land located within 250 feet of a reference line. The reference line means:

- (a) For natural fresh water bodies without artificial impoundments, the natural mean high water level as determined by the Department of Environmental Services.
- (b) For artificially impounded fresh water bodies with established flowage rights, the limit of the flowage rights, and for water bodies without established flowage rights, the waterline at full pond as determined by the elevation of the spillway crest.
- (c) For coastal waters, the highest observable tide line, which means a line defining the furthest landward limit of tidal flow, not including storm events, which can be recognized by indicators such as the presence of a strand line of flotsam and debris, the landward margin of salt tolerant vegetation, or a physical barrier that blocks further flow of the tide.
- (d) For rivers, the ordinary high water mark.

In the case of rivers, the law applies to all fourth order or higher streams of the state with the exception of rivers or river segments designated for management and protection

Statement of Compliance

1) Will the project for which a permit is hereby requested involve construction, land clearing, or other development within the protected shoreland as defined above?

Answer yes or no. Answer **NO**

2) If the project involves construction, land clearing, or other development within the protected shoreland, will it meet or exceed the development standards of RSA 483-B? Answer yes, or not applicable. Answer **N/A**

If not applicable, state why **NOT WITHIN PROTECTED SHORELAND AREA**

(Note, the development standards are not applicable in only three situations: (1) the project is not located in the protected shoreland, (2) the activities are

Certification

As owner or agent for the owner of the subject property, by my signature below, I certify that:

- My responses to questions 1 and 2 above are correct to the best of my knowledge,
- I am familiar with the requirements of RSA 483-B and have knowledge of the development activities which will be undertaken,
- The plans and other information submitted with this permit application provide a complete description of the project and demonstrate how compliance will be accomplished, and
- I understand that false information given in this certification may result in revocation of any permit granted by the Department of Environmental Services as a result of this application, liability for remediation or restoration of the land affected, fines up to \$20,000 for each day of continuing violation, imprisonment or other penalties.

Certified by


Date **FEB. 28, 2005**

Name (print or type) **JEFFREY A. EVANS** owner or agent (circle one)

YOU MUST SUBMIT THE FOLLOWING INFORMATION (Put all information on plans)

- Two (2) sets of scale plans (one inch = 20 feet) (3 sets if designer wants a return copy of plan) showing all lot dimensions and indicating the distance and location of existing and proposed buildings, wells, and waste disposal systems. If the proposed system or well is closer than seventy-five (75) feet to a boundary, you will need to indicate what is on the adjoining lot. If the lot is so large that it cannot be scaled 1" = 20' on your drawing, two copies of a scale plan with a larger scale must also be submitted. The 1:20 scale plan must also contain pertinent elevation data and location of test pits and percolation test holes. All plans must be folded to 8 1/2" x 11". Show areas of exposed ledge or boulders greater than 6" in diameter within 75' of proposed system.
 - Specific directions so that inspector may easily drive to and find the site. Include mileage referenced from intersections or landmarks to this site. This shall be indicated on a USGS quadrangle map or other suitable location plan.
 - Distance and location of nearest surface water in relation to disposal system (must be a minimum of 75' from all lakes, streams, ponds and swamps whether intermittent or year round). If nearest surface water is greater than 75' away a statement to that effect is required.
 - a. Location of proposed and existing drinking water supply lines. Soil Data (to be determined in leaching area for each system indicate where and when tests were taken). Percolation test data including rate and depth of test.
 - b. Test Pit Log:
 - Show depth from original ground surface to the observed water table.
 - Show depth to seasonal high water table (springtime). This may be an estimate based on mottling, NRCS data, etc., (water table must be four (4) feet below the bed during all seasons of the year).
 - Show depth from original ground surface to impermeable substratum (i.e. clay or ledge). Clay and hardpan will be considered impermeable unless proven otherwise. Bottom of effluent disposal area (EDA) must be four (4) feet above any bedrock or any impermeable substratum. P.E. required for edge lots where system will be greater than 600 GPD or for disposal systems greater than 2,500 GPD.
 - Soil description of the predominant soil layers including color notations from the Munsell Soil Color book.
 - c. Soil survey data for the lot. This information is available at the Local Soil Conservation District office. When taken from current soil map, a copy designating locus and site will be acceptable (state reference source).
 - Where fill is required, filled area must extend a minimum of five (5) feet in all directions beyond the edge of the bed at same elevation as top of the bed before tapering off at a 3:1 slope (3 horizontal to 1 vertical). There shall be a minimum of 3" of loam suitable for seeding and proper stabilization of the slope. All topsoil, roots and organic matter under the leaching system must be removed before fill is placed. Show fill details and material specification on cross section.
 1. Number of bedrooms or estimated sewage load in gallons per day.
 2. Ground surface elevations for the lot showing the slope of the land at two foot contour intervals. Sufficient spot elevations are required to verify level lots. Show original and proposed contours. Reference contours to a benchmark located near the proposed systems. This topographical information must appear on the 1:20 scale plan.
 3. Liquid capacity of septic tank, details and materials of construction.
 4. Scale plan of leaching system with construction details and dimensions. Show sill elevations, invert elevations at building exit, inlet and outlet from septic tank, inlet and outlet from distribution box, invert of effluent disposal lines and bottom elevation of effluent disposal area. Inverts must be referenced to your benchmark. Invert may be best indicated on your cross section or profile sections.
 5. Make, type and capacity of sewage pump, pump well, discharge line, siphons, siphon chambers, etc. (when used).
 6. Number of outlets and name of manufacturer of distribution box (all laterals must be directly connected to distribution box, i.e., no tees in the middle of the bed or field will be allowed).
 7. Cross section of leaching trench, leaching bed, or dry well showing all construction details (in leach bed, lines should be uniformly spaced from 3 to 5 feet on center and half of that distance in from the edge of the bed; present requirements for dry wells are 6" minimum of stone around sides of dry well and foot minimum of stone under dry well). Show all fill details on cross section.
 8. Type and size of stone. Must be clean and meet septic stone specifications.
 9. Type, size and manufacturer of effluent disposal pipe.
 10. Type of effluent disposal pipe joints for perforated pipes. (Leach lines shall be interconnected or capped at the end.)
 11. Statement that effluent disposal pipes and bottom of effluent disposal area will be laid as level as possible.
 12. Show a suitable area for a replacement system where available or state that the system may have to be rebuilt in place, if failure occurs.
- NO LIABILITY IS INCURRED BY THE STATE by reason of any approval for construction of individual sewage disposal system plans. Approval by the Department of Environmental Services of individual sewage disposal systems is based on plans and specifications supplied by the applicant. NO GUARANTEE IS INTENDED OR IMPLIED BY REASON OF ANY ADVICE GIVEN BY THE DEPARTMENT OR ITS STAFF.

EFFLUENT DISPOSAL SYSTEM (CROSS SECTION - NOT TO SCALE)




CONSTRUCT EFFLUENT DISPOSAL SYSTEM IN STRICT ACCORDANCE WITH CURRENT ENVIRO-SEPTIC LEACHING SYSTEM DESIGN AND INSTALLATION MANUAL


NOTES:
- TOPSOIL AND ORGANICS TO BE REMOVED FROM DISPOSAL AREA PRIOR TO PLACING SAND OR FILL.
- FINAL GRADING TO SHED SURFACE WATER AWAY FROM SYSTEM COMPONENTS.

INSTALLERS NOTE: SWING TIES ARE TO OUTSIDE OF THE SAND ENVELOPE

EFFLUENT DISPOSAL AREA CROSS SECTION - NOT TO SCALE



LOCATION MAP NOT TO SCALE



SOIL INFORMATION

U.S.D.A./N.R.C.S. (S.C.S.) COUNTY OF ROCKINGHAM
38B ELDRIDGE FINE SANDY LOAM
SHEET 20 DATED OCTOBER 1994

TEST PIT DATA A

DUG ON 2/09/2005
TEST PITS WITNESSED BY M. COUMO OF R.C.C.D.

Ap	0-10"	10YR3/3 FINE SANDY LOAM
B	10-26"	2.5Y5/6 FINE SANDY LOAM
C	26-65"	2.5Y5/6 STONY SANDY LOAM

REDOX CONCENTRATION AT 26" E.S.H.W.T.

TEST PIT DATA B FOR RESERVED SITE

DUG ON 2/09/2005
TEST PITS WITNESSED BY M. COUMO OF R.C.C.D.

Ap	0-10"	10YR3/3 FINE SANDY LOAM
Bw	10-18"	2.5Y5/6 FINE SANDY LOAM
B2	18-26"	2.5Y5/3 VERY FINE SILT LOAM
C	26-65"	2.5Y5/3 SILT LOAM

REDOX CONCENTRATION AT 26" E.S.H.W.T.

1" IN 8 MINUTES AT 24" 2/9/05

FILL NOTE:

REMOVE ALL TOPSOIL AND ORGANIC MATTER, TREES, STUMPS, SHRUBS, BOLLERS AND DEBRIS FROM PLACING FILL MATERIAL BELOW DISPOSAL AREA. THIS INCLUDES AREA BELOW FULL SETBACKS AND 3:1 SIDE SLOPES. FILL MATERIAL TO BE CLEAN SAND AND GRAVEL FREE OF TOPSOIL, LOAM, CLAYS, SILTS AND ORGANIC MATERIALS AND ROCKS OVER 6" IN ANY DIMENSION.

FILL UNDER BED IS TO BE WASHED MEDIUM TO COARSE TEXTURE SAND WITH AN EFFECTIVE SIZE OF 0.25 TO 2.0 MM MAXIMUM SIZE FINES PASSING A #60 SIEVE. SEE ENVIRO-SEPTIC LEACHING SYSTEM DESIGN & INSTALLATION HANDBOOK.

OWNER TAKE NOTE:

- ENV-WS 1023.01 SEPTIC TANK INSPECTION AND PUMPING REQUIREMENTS.
 - SEPTIC TANKS SHALL BE INSPECTED FOR ACCUMULATION OF SLUDGE AND SURFACE SCUM AT LEAST ONCE EVERY YEAR.
 - WHEN THE COMBINED THICKNESS OF THE SLUDGE AND SURFACE SCUM EQUAL 1/3 OR MORE OF THE TANK DEPTH, THE TANK SHALL BE PUMPED BY A LICENSED SEPTIC TANK PUMPER.
- THIS SYSTEM HAS BEEN DESIGNED FOR THE DISPOSAL OF SEWAGE PRODUCED BY HUMANS AND NORMAL KITCHEN, BATHROOM, AND LAUNDRY WASTE ONLY. ADDITION OF ANY WASTE OTHER THAN NOTED ABOVE MAY RESULT IN PREMATURE FAILURE OF THE SYSTEM, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - WASTE PRODUCED WITH A GARAGE GRINDER/DISPOSAL, DRAIN WATER FROM AN OVERSIZED TUB, WATER CONDITIONER FLUSH, EXCESSIVE COOKING FAT, PAINTS OR OTHER CHEMICALS, OR ANY COMMERCIAL WASTE.
 - CONSULTATION WITH A LICENSED DESIGNER IS NECESSARY IF ADDITIONAL USE OR A CHANGE IN USE IS PROPOSED AT ANY TIME.
- THIS SYSTEM HAS NOT BEEN DESIGNED TO, NOR SHALL IT BE ALLOWED TO, BE DRIVEN UPON, OR PARKED UPON, NOR SHALL ANY VEHICLES, LIVESTOCK, OR ANY OTHER HEAVY OBJECTS BE ALLOWED ON THE LEACHFIELD OR THE SEPTIC TANK.
- THERE SHALL BE NO GARBAGE DISPOSAL USED WITH THIS SYSTEM.

GENERAL NOTES:


- DESIGN INTENT: THE BOTTOM OF THE EFFLUENT DISPOSAL SYSTEM (EDS) SHALL BE CONSTRUCTED AT ELEVATION 75.5, AND THERE IS APPROXIMATELY 1.0 FEET ABOVE ORIGINAL GRADE ON THE HIGH CONTOUR OF THE DESIGNED EFFLUENT DISPOSAL SYSTEM.
- DESIGN CRITERIA AND CALCULATIONS:
 - 3 BEDROOM HOME
 - ~ 8 MINUTES PER INCH PERCOLATION RATE
 - PERC RATE 1" IN 8 MINUTES, 3 BEDROOM/1000 LINEAR FEET OF ENVIRO-SEPTIC PIPE REQUIRED, 3 ROWS X 80' = 150' PROVIDED
- USE 3 ROWS EACH ROW TO BE 50' OF ENVIRO-SEPTIC PIPE ROWS TO BE 2.0' ON CENTER. ENVIRO-SEPTIC PIPE TO BE ENCLOSED IN A SAND ENVELOPE 1.0' DIA' SUPPLIED BY WASTE INC. CONCORD, NH.
- TO THE BEST OF MY KNOWLEDGE, THERE ARE NO VERY POORLY DRAINED SOILS WITHIN 75' OF THIS SYSTEM AND NO POORLY DRAINED SOILS WITHIN 50' OF THIS SYSTEM.
- IF FAILURE OCCURS, THIS SYSTEM IS TO BE REBUILT IN-PLACE.
- SEAL ALL PIPE PENETRATIONS AT CONCRETE PRODUCTS AS WELL AS ALL CONCRETE JOINTS AND SEAMS WITH AN ACCEPTABLE NON-SHRINK, WATER-STOPPING (AND ROOF TAP).
- THIS IS NOT A WARRANTY SURVEY.
- INSTALLER NOTE: IT SHALL BE THE RESPONSIBILITY OF THE INSTALLER TO NOTIFY THIS FIRM OF ANY ERRORS OR OMISSIONS OR VARIATIONS WITH RESPECT TO THIS DESIGN, AND TO DO SO IMMEDIATELY UPON FINDING OR BE AWARE OF SUCH.
- WELL STATUS: WATER IS PROVIDED FROM AN ON SITE INDIVIDUAL WELL.
- SEPTIC TANK TO BE 1250 GAL. (ENV-WH 1010.02) CONCRETE FROM EPSOM PRECAST EPSOM, NH, OR EQUAL. SEPTIC TANK IS TO HAVE POLYLOK MODEL NO. PL122 EFFLUENT FILTER, INSTALLED PER SUPPLIERS REQUIREMENTS IN PLACE OF THE OUTLET Baffles.
- DISTRIBUTION BOX TO BE CONCRETE FROM EPSOM PRECAST, OR EQUAL, 18" DIA. 12" INCH FLOW EQUALIZER IN D-BOX AVAILABLE FROM EPSOM PRECAST.
- APPROVAL OF THIS PLAN ALLOWING CONSTRUCTION OF ENVIRO-SEPTIC DESIGN ONLY. CONSTRUCTION OF CONVENTIONAL SYSTEM REQUIRES SEPARATE DESIGN, DRAWING, SUBMISSION, AND INSPECTION APPROVAL.

INDIVIDUAL SEWAGE DISPOSAL SYSTEM FOR

RICHARD STEARNS
UNION ROAD
STRATHAM, NEW HAMPSHIRE

TAX MAP 18 LOT 54
R.C.R.D. BK. 4353 PG. 443
SCALE 1"=20' DECEMBER 2004

GRAPHIC SCALE




PREPARED BY

JEFFREY A. EVANS, LAND CONSULTANT
LICENSED PROFESSIONAL, LAND SURVEYOR 517, FORESTER 162
WETLAND SCIENTIST 105, SEPTIC SYSTEM DESIGNER 64
P.O. BOX 522 SOUTH SUTTON, NH 03273 (603) 927-4696

UNION ROAD

CUT ON POLE
ELEV. 77.42' 0"



CA 2005070310